

High Street School, War Memorial Arch, Estimate

Wainwright&Co Stonemasons

6-Dec-19

Task	hours	units	cost	materials	total	comments
1 To clean monument with Doff steam cleaning system			1	577	577	
2 Repoint missing mortar joints and rebed dislodge cap stone. Spalling stones that are loose: remove, treat rust, rebed stones.	24			55	1320	
3 Tap back lead lettering	1.5			62	93	
4 Reinststate lead letters		3		22		66 confirm letters once cleaned and tapped back
5 Applying biocide, Quadclean	1.5			55	50	132.5
6 Site visits and inspection	4			55		220
7 Painters estimate \$2 - 2.5k + 12%	1			2500		2800
8 Engineer estimate 3 days at \$70perhour plus materials + 12%	21			70	200	1846.4
9 Removing/reinstating fencing	16			62		992
10 Setting up mini scaffold/H&S	8			55		440
11 Repair work to render of concrete base wall	8			62		496 needs some trials to determine finish look
Total, GST excluded						8982.9